

**BILL OF QUANTITY FOR Civil And And Plumbing For THE PROPOSED INTERIORS**

Sr.No.	Client: Acuite	Qty	Unit	Rate	Amount
	<b>Civil And Plumbing work</b>				
<b>A</b>	<b>Toilet</b>				
1	Waterproofing in Toilet	40	SFT		
2	6 Inch PCC on Floor	40	SFT		
3	WC And Piping (consealed tank)		Lumsum		
4	Wall Tile ( Cera/RAK/Kajaria)	185	SFT		
5	wash basin Counter top granite (Black)	15	SFT		
6	Wash Basin ( Wash Basin parryware/ or similar)		Lumsum		
7	Plumbing fittings and Piping ( Basin Connection, WC Jet Spray with Tap, drainage piping ) fittings will be jaguar/Parryware or similar		Lumsum		
5	Door Framing (Black Granite and smooth Polishing)	56	SFT		
6	Plumbing connection for Geyser		Lumsum		
7	Shower with geyser connecting		Lumsum		
<b>B</b>	<b>Pantry</b>				
1	Kitchen Counter Top ( Black Granite and Bottom in marbar)	22	SFT		
2	Kitchen Sink SS finish with drainage piping		Lumsum		
3	Kitchne Fitting for Aquaguard and Sink tap ( Fitting will be Jaguar/Parryware or similar)		Lumsum		
4	2 by 2 Wall tile above kitchen Top (Same Floor Tile)	88	SFT		
<b>C</b>	<b>Floor Tile work</b>				
1	Floor Waterproofing (Pedlite)	1495	SFT		
2	2 inch PCC on floor	1495	SFT		
3	Providing and laying 600 mm x 600 mm Vitrified Double charged Tiles for Flooring of approved make and sample in pattern as per detailed drawings	1195	SFT		
4	Scutting tile 3 inch on full wall side same tile of flooring	220	RFT		
5	Door Floor Spring Machine Cutting	10	Nos		
6	Pantry and toilet wall breaking and repairing for AC duct		Lumsum		
	<b>Total</b>				