BILL OF QUANTITY FOR Civil And And Plumbing For THE PROPOSED INTERIORS							
Sr.No.	Client: Acuite	Qty	Unit	Rate	Amount		
	Civil And Plumbing work						
В	Pantry						
1	Kitchen Counter Top (Black Granite and Bottom in marbar)	28	SFT		0		
2	Kitchen Sink SS finish with drainage piping		Lumsum		20000		
3	Kitchne Fitting for Aquaguard and Sink tap (Fitting will be Jaguar/Parryware or similar)		Lumsum				
4	2 by 2 Wall tile above kitchen Top (Same Floor Tile)	35	SFT		0		
C	Floor Tile work Door Floor Spring Machine Cutting	7	Nee				
1		7	Nos		0		
	Wall construction 6" thk - Siphorex Autoclaved Aerated Concrete (AAC) Blocks and plastering it with						
2	8mm thk cement plaster	132	Sft		0		
	Wall construction 6" thk - Siphorex Autoclaved Aerated Concrete (AAC) Blocks and plastering it with						
3	8mm thk cement plaster	72	Sft		0		
	Wall construction 6" thk - Siphorex Autoclaved Aerated Concrete (AAC) Blocks and plastering it with						
4	8mm thk cement plaster	84	Sft		0		
	Wall construction 6" thk - Siphorex Autoclaved Aerated Concrete (AAC) Blocks and plastering it with						
5	8mm thk cement plaster	24	Sft		0		
	Tatal				20000		
	Total				20000		
D	FALSE CEILING						
		Qty	Unit	Rate	Amount		
1	Grid Ceiling and Gypsum Ceiling with designer ceiling	2013	SFT		0		
	AC duct ceiling	2013	RFT		0		
2	Light Gala Cutting	30			0		

		_		
E	PAINTING & POLISH WORKS WORKS			

1	Providing and applying two coats of approved shade of royale luxury emulsion paint of approved make to give an even shade over a coat of suitable primer to Interior walls and concrete surfaces including preparation of the etc., complete FOR CEILING & Walls surface to receive the coats	3800	SFT	0
2	Wooden Patti Poilish or paint in partition	1010	RFT	0
	Total C/O to Abstract			0