BILL OF QUANTITY FOR ELECTRICAL WORKS FOR THE PROPOSED INTERIORS						
r.N	Client:SMERA	Qty	Unit	Rate	Amount	Remarks
А	Supply and providing of all internal electrical work for main distribution board.					
	All Workstation will have 2 model plate 1 socket 1 switch and 1 USB 2.5mm Cable					
	All Workstation will have 2 Socket 2 Switch Bellow the table (2.5mm Cable)					
	4 Workstation table will have 4 Cat6 Cable					
	All Cabin Will have 1 Cat 6 Cable	1,495.00				
	All Cabin Will have 8 Model Plate 2 socket 1 USB and 2 Light switch 1 Switch					
	require socket will be require in pantry					
	Toilet will have 1 light and 1 ceiling exhaust Fan which will be operted on sensor base					
	Toilet will have gyser connection					
	AC electrical work and MCB from electrical board to Outdoor unit and AC remote Cabeling					
	All switches will be GM Brand selected by Client					
	4 Cat 6 For Camera till the electrical room					
	4 Door Access Control Cabeling 2 each					
	2 CAT 6 Cabel for Wifi router on ceiling					
	1 CAT 6 Cabel at workstation area for printing					
	All Cabel will be consealed on wall no wire will be visible					
	Electrical Main Distribution Board					
В	Lights					
	36W 2 by 2 Ceiling light 4000K	14				
	15W Sq Light 4000K	7				
	15W Round 4000K	4				
	6W Spot light 3000K	3				
	GRAND TOTAL				0	1