

BILL OF QUANTITY FOR ELECTRICAL WORKS FOR THE PROPOSED INTERIORS						
Sr.No	Client:Acuite	Qty	Unit	Rate	Amount	Remarks
A	Supply and providing of all internal electrical work for main distribution board.		Nos			
	All Workstation will have 2 model plate 1 socket 1 switch and 1 USB 2.5mm Cable	48	Nos			
	All Workstation will have 2 Socket 2 Switch Bellow the table (2.5mm Cable)	48	Nos			
	Data point for Workstation, Cabin, Conference room and other point	65	Nos			
	Voice Point (Workstation, Cabin, Conference room, Pantry) (Dlink Cat6)	55	Nos			
	All Cabin Will have 8 Model Plate 2 socket 1 USB and 2 Light switch 2 Switch	3	Nos			
	Visitor room will have 6 model plate both side of the table	2	Nos			
	Visitor room will have 1 HDMI Cable from TV to table	1	Nos			
	Visitor room TV Point on wall	1	Nos			
	15A extra point as per requirement	5	Nos			
	Conference room table will have 8 model plate both side	2	Nos			
	Conference room Table will have 1 HDMI Cable from to to Table	2	Nos			
	Pantry will have 15A sockets wherever require	7	Nos			
	Workstation area ceiling light 2 by 2	6	Nos			
	Cabin and other area will have 16W 4000k Panel ligh in seq and spot light	19	Nos			
	Reception area designer ceiling strip light		Nos			
	Conference room Ceiling panle light and Spot light and 4000K	12	Nos			

	Conference room LED Strip Light		Nos			
	AC electrical work and MCB from electrical board to Outdoor unit and AC remote Cabeling		Nos			
	Note:					
	All switches will be GM Brand selected by Client					
	Voice and data cable should be Cat 6 (Dlink Brand)					
	4 Door Access Control Cabeling 2 each					
	2 CAT 6 Cabel for Wifi router on ceiling					
	1 CAT 6 Cabel at workstation area for printing					
	All Cabel will be consealed on wall no wire will be visible					
	Electrical Main Distribution Board					
	GRAND TOTAL				0	