No Client: Acuite	Qty	Unit	Rate	Amount
A SMOKE DETECTOR - Ravel / Agni make	14	Nos		0
Heat detector	1	Nos		0
1. System Sensor Fire Alarm System 2 zone panel with LED Display supply, installation & programming 1Nos 8,500/- 8,500/-	1	Nos		0
4. 1.5 2Core FRLS Armoured Polycab Cable	250	Meter		0
B FIRE SPRINKLER SYSTEM	1843	SFT		0
Supplying, installing, testing and commissioning of G.I. Pipes confirming to IS 1239 Pt - I Heavy grade with painting, suitable type of supports (for above 50 mm dia, shall be fabricated by M.S. Channel / Angle / Flats etc.), anchor fasteners, bolts nuts (jindal,zenith.tata) - 2mm dia - 100mm dia				
Supplying, installing, testing and commissioning conventional Sprinkler quartzi bulb type with 15mm screwed end connection of 68 deg. C. temperature ratin 80 and orifice shall not be less than 6mm.Sprinklers shall be <u>UL Listed / FM</u> <u>approved HD MAKE</u>				
Stainless steel corrugated flexible pipe(hose) for dropping sprinklers below fals ceiling, pipe shall be 16 bar pressure rating and 450 mm long 25 mm dia with union / reducer collar, clamps etc. as required/L APPROVED	se			
Fire extinguisher 2KG	2.00	Nos		
GRAND TOTAL				0