

BILL OF QUANTITY FOR ELECTRICAL WORKS FOR THE PROPOSED INTERIORS						
Sr.No	Client:SMERA	Qty	Unit	Rate	Amount	Remarks
	Supply and providing of all internal electrical work for main distribution board.					
	All Workstation will have 2 model plate 1 socket 1 switch and 1 USB 2.5mm	4147				
	All Workstation will have 6 model plate with 2 Socket 2 Switch Bellow the table (2.5mm Cable)					
	each workstation table will have 6 Cat6 Cables					
	All Cabin Will have 2 Cat 6 Cable (1 for data and 1 for Voice)					
	3 Cabin Will have 6 Model Plate 2 socket 1 Switch 1 USB both side and 2 model plate with 2 siwtch for Light					
	Toilet will have 1 light and 1 ceiling exhaust Fan which will be operted on sensor base					
	Conference room will have 8 ceiling light					
	Conferecne room will have 6 model plate 2 both side bellow the table which has 2 socket and 1 switch and 1 USB					
	Mini Conference room will have 6 light					
	Mini Conference room will have 6 model plate both side bellow the table which has 2 sockets and 1 switch and 1 USB					
	UPS and Server room connetion					
	1 Toilet will have gyser connection					
	Training room will have 6 model 8 Plate which will have 2 socket 1 15 A and 1 5 A with 2 switch					
	Pantry room will have 6 model 8 Plate which will have 2 socket 1 15 A and 1 5 A with 2 switch					
	AC electrical work and MCB from electrical board to Outdoor unit and AC remote Cabeling					
	All switches will be GM Brand selected by Client					
	4 Cat 6 For Camera till the electrical room					
	4 Door Access Control Cabeling 2 each					
	2 CAT 6 Cabel for Wifi router on ceiling					
	1 CAT 6 Cabel at workstation area for printing					
	All Cabel will be consealed on wall no wire will be visible					

	Electrical Main Distribution Board					
	UPS DB setup					
	Raw Power DB require					
	Main Incomer					
B	Lights					
	36W 2 by 2 Ceiling light 4000K	14				
	15W Sq Light 4000K panel light	20				
	15W Round 4000K Panel light	20				
	6W Spot light 3000K	10				
	GRAND TOTAL				0	