

BILL OF QUANTITY FOR Civil And And Plumbing For THE PROPOSED INTERIORS

	Sr. No.	Client: Acuite	Qty	Unit	Rate	Amount
A		CIVIL AND PLUMBING WORK				
	1	Full Office Dismantal Charges				
	a	Table				
	b	Glass Partition				
	c	Toilet				
	d	Cabin				
	e	Main door				
	f	Other				
	g	removing all the material				
	h	Removing the tiles				
	2	Providing and laying 600 mm x 600 mm Vitrified Tiles for Flooring of approved make and sample in pattern as per detailed drawings	340	SFT		0
	3	Scutting tile 3 inch on full wall side same tile of flooring	80	RSF		0
	4	Flooring Plaster for Tiling work smoothness	340	SFT		0
	5	Plaster on wall	124	SFT		0
	6	Window Granite Framing	28	SFT		0
	7	Pantry				0
	a	Granite Platform for Pantry (Good quality Black)	6			0
	b	Sink for pantry	1	nos		0
	c	Piping for sink and water purifier	Lumsum			0
	d	Tap for sink	1	Nos		0
	e	Tap for Water purifier	1	Nos		0
	f	PRV for water purifier	1	Nos		0
	g	4 inch wall making (By ACC Block) near pantry area	50	Sft		0
		Tiling on kitchen top	6	Sft		0
						0
	8	Toilet				0
	a	4 inch wall making (By ACC Block) for 2 toilet	200	Sft		0
	b	Toilet WC with Piping (Company Brand Jaquar or Parryware)	2	Sft		0
	c	Basine with Counter top (Jaquar or Parryware)	2	Nos		0
	d	Toilet fitting (Parry ware and Jaquar) Pipe should be copper inside	2	Nos		0
	e	Granite Frame on door 1 (Good quality Black)	35	Sft		0
		Wall tile	252	Sft		0
						0
B		FALSE CEILING				
	1	2 by 2 tile ceiling work	340	Sft	0	0
C		PAINTING & POLISH WORKS WORKS				
		Providing and applying two coats of approved shade of royale luxury emulsion paint of approved make to give an even shade over a coat of suitable primer to Interior walls and concrete surfaces including preparation of the etc., complete. - FOR CEILING & Walls surface to receive the coats	950	Sft	0	0
		Total C/O to Abstract				